

**STATE OF VERMONT  
PUBLIC SERVICE BOARD**

Docket No. \_\_\_\_\_

Petition of UPC Vermont Wind, LLC for a Certificate of )  
Public Good pursuant to 30 V.S.A. section 248, )  
authorizing it to construct up to a 52 MW wind electric )  
generation facility, and associated transmission and )  
interconnection facilities, in Sheffield and Sutton, Vermont, )  
and operate the same. )

**PREFILED DIRECT TESTIMONY OF  
RALPH NELSON**

**ON BEHALF OF UPC VERMONT WIND, LLC**

February 21, 2006

Summary:

Mr. Nelson provides information on site design, stormwater, soil erosion, and land impacts as they relate to the Sheffield Wind Farm's compliance with the water pollution, waste disposal, soil erosion, water supply, and traffic criteria under section 248(b)(5).

1 **Q Please state your name and occupation.**

2 Response: My name is Ralph D. Nelson, Jr., PE. I am currently an employee of  
3 Devine Tarbell and Associates (DTA). I work on civil engineering and permitting  
4 for various residential, commercial and industrial site design projects as a Senior Civil  
5 Engineer.

6 **Q Please describe your qualifications and experience.**

7 Response: Please refer to my resume, attached as *Exhibit UPC-RN-1*. I was  
8 educated at Northeastern University, and received my BSCE in 1981. I am a  
9 registered professional engineer in the State of Vermont. I have 23 years of  
10 experience as a civil/structural, hydraulic engineer in the planning, licensing and  
11 permitting support on hydroelectric and heavy industrial projects. This experience  
12 includes project and lead engineering experiences on several wind projects.

13 DTA has been contracted by UPC Vermont Wind, LLC (UPC), to contribute to the  
14 design work at the Sheffield Wind Farm. To that end, I have familiarized myself  
15 with potential wind turbine components and Vermont's permitting processes.

16 **Q Have you previously testified before the Public Service Board?**

17 Response: No, I have not testified before the Vermont PSB.

1    **Q    What is the purpose of your testimony?**

2            Response: I will testify about site design, stormwater, soil erosion, and land impacts  
3            as they relate to the Sheffield Wind Farm's compliance with the water pollution,  
4            waste disposal, soil erosion, water supply, and traffic criteria under section 248(b)(5).

5    **Q    Please summarize the investigations, analyses, planning, and engineering you**  
6            **conducted regarding the proposed Sheffield Wind Farm.**

7            Response: DTA was responsible for the coordination of various subcontractors  
8            involved in the mapping of sensitive environmental resources including wetlands;  
9            rare, threatened and endangered species; and large mammal habitat, as well as the  
10           aerial photogrammetry used for the Project. DTA used this information, along with  
11           the construction and operation requirements provided by UPC, to prepare 20%  
12           design plans for the Project. I believe that this level of design is adequate to assess  
13           impacts discussed later in this testimony.

14   **Q    What was the objective of the design work that you performed?**

15           Response: The objective was to design project roadways that will provide adequate  
16           site access for both construction and operation of the wind farm, as we avoided  
17           impacts to sensitive environmental resources within the project area. Further, as part  
18           of these preliminary design plans, we have considered various means to control and  
19           reduce the stormwater flows and the potential for erosion. As discussed below the  
20           exact details of stormwater and erosion control will be incorporated in the final  
21           design.

1    **Q    Please describe the components of DTA’s work.**

2            Response: DTA has prepared preliminary plans that show the turbine locations, the  
3            extent of clearing, the turbine foundations, the location of the substation required to  
4            connect to VELCO’s 115 kV transmission line, and the local access roads that will  
5            be required for the installation and operation of this facility. These drawings were  
6            prepared based on the 2-ft contour aerial survey mapping of a “corridor” along the  
7            ridgelines and existing roads performed by Aerial Survey and Photo, Inc. of  
8            Norridgewock, Maine. See *Exhibit UPC-RN-2*. Other design features, such as the  
9            location of the underground and overhead electrical collection system is being  
10           designed by others (see the prefiled direct testimony of Daniel Crocket).

11                    In addition, DTA has prepared a framework of the erosion prevention and  
12            sediment controls that could be utilized for construction of this Project. This  
13            document is conceptual and not meant to be the final, site-specific plans that will  
14            need to be submitted to ANR as part of its permitting requirements. This conceptual  
15            plan is attached as *Exhibit UPC-RN-3*. We have not proceeded with the final  
16            design level efforts at this time because the layout and construction aspects may  
17            change during the section 248 process.

18    **Q    Please describe the results of the iterative design process that has been**  
19    **undertaken.**

20            Response: Developing the layout of this project is best viewed as having been a  
21            “living” design process. The original turbine locations were proposed by UPC based,

1 in part, on elevations and economics. One of the first iterations of the project layout  
2 included more than 35 wind turbines. We provided a project “envelope”  
3 encompassing all the anticipated impact areas for the project along with a 300-ft  
4 offset. This layout envelope was investigated by environmental and engineering  
5 experts retained by UPC. For a variety of reasons, including wetlands, habitat, visual,  
6 and engineering considerations, the number of turbines has been reduced from 35 to  
7 the current 26 and has resulted in the relocation of the turbines in many areas to  
8 minimize impacts to the extent practicable. This process has been on-going and the  
9 current proposal avoids and minimizes impacts to a very great extent and to the  
10 point where they do not cause an undue adverse impact to the environment. That  
11 being said, additional modifications may be considered, in consultation with ANR  
12 and through the 248 process, to further reduce impacts on bear-scarred beech trees  
13 and possibly on the Class 3 wetlands.

14 The resulting layout was designed to use the existing logging road network as  
15 much as feasible to minimize the impacts to wetlands, streams and wildlife habitat as  
16 much as practical. On the project plans and layouts provided as part of this permit  
17 application, the on-site roads are identified on the plans as those that will be  
18 upgraded for use and those to be constructed. The existing roads to the ridgelines  
19 were constructed to support logging operations, and the Project’s proposed use is  
20 not dissimilar. Logging vehicles are very large and heavy. This is typically heavier on  
21 a per axial basis than the proposed wind project loads. In contrast, our proposed  
22 access vehicles require more grade and dimensional control for the roads due to the  
23 size of the cargo. Therefore, the upgrades on the existing access roads are

1 anticipated to include, in part, slight widening of the road surface in some areas,  
2 minor clearing of vegetation along the shoulder and overstory edges and  
3 repair/replacement or reinforcement of the culverts.

4 The proposed new access roads along the ridgelines and between turbines are  
5 designed based on the dimensional controls from construction vehicles, including  
6 the construction cranes and trucks. The construction of the proposed roads will  
7 included clearing of the vegetation, grubbing of the stumps and roots, removal of  
8 any topsoil and overburden, fill or removal of rock as needed to make the required  
9 maximum finish grade of 15% and the addition of cover material to allow movement  
10 of construction equipment. The final roads will be a nominal 16 feet wide. Those  
11 roads requiring construction crane passage will have additional 10 foot shoulders on  
12 both sides, creating a temporary construction width of 36 feet. Following the  
13 completion of construction these shoulders will be allowed to naturally re-vegetate.

14 The project considers two access points off of the local public road network.  
15 For the southern array access will be gained via an existing access road off of  
16 Hardscrabble Road. For the northern array access is via an existing logging road off  
17 of Dareios Road. Further discussion of the access routes is provided in the prefiled  
18 direct testimony of Cowan/Rowland/Vavrik.

19 In addition to the road network, I was responsible for assisting the UPC  
20 meteorologist in determining the final locations of the turbines along with the  
21 location of the substation and maintenance building. The substation was originally

1 located on the northern side of the access road depicted on the project layout. This  
2 substation was relocated twice to the south to avoid wetland impacts.

3 The maintenance building will serve as the office and warehouse for  
4 operation of the Project. The maintenance building's location is to be finalized  
5 following additional field work to delineate wetlands and other potential impacts.  
6 The two proposed on-site locations include: 1) at the edge of the existing gravel pit  
7 adjacent to the existing access road which runs from the substation to the northern  
8 array; and 2) further uphill on the existing access road for the northern array in an  
9 area of cutover land. In addition, off-site leased locations are being investigated by  
10 UPC. The final location of this building will be, in part, dictated by adequate soils  
11 for on-site septic disposal and avoiding habitat impacts. The maintenance building  
12 will have approximately 6,000 feet of cold storage and a heated office area. A water  
13 well will be installed to provide potable water for workers and for sanitary flows. An  
14 on-site septic disposal system will be designed and constructed. The water and  
15 wastewater systems will be designed in compliance with the local and the State of  
16 Vermont rules for such systems and good engineering practice.

17 **Q Will the project cause undue water pollution, and will the project meet**  
18 **all applicable state regulations regarding stormwater and waste disposal?**

19 Response: The project will not cause undue water pollution. The project will meet  
20 all applicable stormwater and waste disposal regulations.

1           The perceived *potential* water pollution sources include, but are not limited to,  
2 motorized equipment fuel or oil, hydraulic fluid, eroded soil and/or roadway  
3 materials, turbine lubricants or miscellaneous debris. Specifics will be elaborated  
4 upon prior to construction through the Vermont NPDES Construction General  
5 Permit's Notice of Intent but at this time I expect that the project will address the  
6 following element to protect water resources:

- 7           (1) Fuel storage or fueling equipment will be located a safe distance from wetland  
8 resources and surface waters;
- 9           (2) Prompt cleanup of any spills of fuel, motor oil, hydraulic fluid or cooling oil, and  
10 documentation of same. During the construction phase, the potential sources of  
11 groundwater contamination will be fuel, and hydraulic and lubricating oils used  
12 by the operation of vehicles and construction equipment. Spills of these  
13 substances from vehicles or equipment are typically small and of short duration  
14 and, when properly cleaned-up, should not pose any risk to water quality. The  
15 contractors and subcontractors that will access the project site will be trained in  
16 UPC's protocol for responding to, and preventing spills. The protocol will  
17 provide descriptive procedures for safe storage and handling of materials in  
18 order to prevent spills and, in the event of a spill, spill reporting procedures,  
19 emergency contact telephone numbers (including state and federal environmental  
20 agencies), and oil spill cleanup guidelines. In the event of a spill of oil or  
21 hazardous material, employees will be trained to promptly contain, report, and  
22 cleanup the spill in accordance with these procedures. In addition, as a standard

1 operation procedure, all operational vehicles are planned to carry an oil spill kit  
2 that contains material for conducting initial containment and cleanup of spills.  
3 Based on normal operations and the characteristics of a routine spill cleanup,  
4 there is no need for any ongoing groundwater monitoring.

5 Post-construction operation and maintenance of the wind turbines and  
6 substation will involve the use of common lubricants, hydraulic fluids, petroleum  
7 products, or other chemical products. These products are typically integral to the  
8 equipment used on site, such as in the nacelle, oil-filled transformers in the  
9 substation, capacitors, batteries, or other apparatus. Based on our understanding  
10 of the volumes of materials utilized in each turbine and/or typically stored within  
11 the maintenance building as part of the operations, only the transformer within  
12 the substation triggers the requirements of an SPCC plan. The SPCC plan will  
13 be developed within six months of beginning oil storage activities at the site.  
14 VELCO, who will own the transformer, will be responsible for developing and  
15 implementing the SPCC Plan.

16 (3) Secure containers for all chemicals and petroleum products on site. Storage of  
17 containerized chemical products used for maintenance on turbine and substation  
18 sites is limited and incidental, and will be contained in the operational and  
19 maintenance building, the substation's control house building (if necessary), or  
20 off-site. Examples of these products include lubricating oils, aerosol lubricants,  
21 non-chlorinated dielectric solvents, and pesticides (hornet or wasp spray). Bulk

1 quantities of petroleum products, pesticides, herbicides, fertilizer, or other  
2 products will not be stored on site;

3 (4) Erosion Prevention and Sediment Control, as discussed in more detail below.

4 (5) Class A Waters: Within the Passumpsic basin, the only Class A waters are those  
5 located above 2500 feet. There are no waters within the project area located  
6 above 2500 feet. Turbine T-3 is located at elevation 2522', but represents only  
7 one acre of temporary clearing and 0.1 acres of permanent impervious surfaces.  
8 Five stream crossings of Class B waters at lower elevations will be required, as  
9 shown on the site plans.

10 **Q Please describe how stormwater will be addressed for the Project.**

11 Response: Due to creation of more than one acre of impervious surface from the  
12 construction of the turbine foundations and the like, a permit from the State of  
13 Vermont's stormwater program for new development will be required.

14 I have reviewed the treatment standards contained in the Vermont Stormwater  
15 Manual and have met with representatives of this program on a number of  
16 occasions. All stormwater management aspects of this project will be designed for  
17 Water Quality, Recharge, Channel Protection, Overbank Flood and Extreme Storm  
18 conditions. Subject to further discussion with ANR, the preliminary design concepts  
19 are as follows:

1 (1) Water quality treatment will be designed to remove 80% of total suspended  
2 solids and 40% of total phosphorus load. The Water Quality Treatment  
3 Standard will be addressed during final design using combinations of stormwater  
4 credits, such as non-rooftop disconnection credits for discharge to a vegetated  
5 pervious area, the natural area conservation credit, the use of infiltration devices,  
6 and the use of water quality ponds where required.

7 (2) Channel Protection. The final design of the project will address the Channel  
8 Protection Treatment Standard through the combined use of stormwater ponds,  
9 stormwater wetlands, infiltration, filtering practices, and open channel practices.  
10 There may be areas of the project that qualify for the Channel Protection  
11 Treatment Standard waiver where post-development discharges are less than 2  
12 cfs to qualifying drainages. Wherever possible, stormwater will be directed off  
13 the new impervious surfaces through sheet flow and across a vegetated buffer.  
14 Any concentrated flow will be frequently channeled beneath and away from the  
15 road, to both reduce the accumulating stormwater volume and to better maintain  
16 the existing hydrology. In addition, the nearer to wetland resources and other  
17 receiving waters, the more detailed the analysis will be for channel protection and  
18 flow attenuation. Even if the criteria for a waiver for Channel Protection are  
19 met, permanent controls of some nature will be provided.

20  
21 (3) Groundwater Recharge Treatment is typically provided via an infiltration trench  
22 or surface sand filters, or dry swales or grass channels. Wherever possible,  
23 nonstructural groundwater recharge methods will be employed; examples include

1 sheet flow into stream buffer or open vegetated swales. The standard will be  
2 addressed during the final design, but it is anticipated that the standard will be  
3 met through the discharge of site runoff across permeable areas, rip-rapped  
4 slopes, or wood-chip covered areas.

5  
6 (4) Overbank Flood Protection and Extreme Flood Protection will likely be  
7 provided by the same structures as those for channel protection. Initial analysis  
8 of the site hydrology shows that the peak flow values and runoff volumes for the  
9 1-, 2-, 10-, and 100-year precipitation events from the site are not increased  
10 significantly, owing to the small increase in impervious area and the location of  
11 the new impervious at the uppermost portions of the basin. I anticipate that the  
12 new stream crossings will be designed to provide detention in order to reduce  
13 peak flow values, further reducing downstream peak flow values. The Flood  
14 Standards will be reviewed in the final design process. Vermont generally  
15 requires a downstream analysis for projects of more than 50 acres and where on-  
16 site impervious cover is greater than 25% or when deemed appropriate by the  
17 ANR. If required by ANR, the final design will incorporate a downstream  
18 analysis for the 10-year and 100-year event following the 10% rule.

19  
20 **Q Please describe how waste disposal and oil containment will be addressed for**  
21 **the Project.**

22 Response: The operations and maintenance building sanitary flows will be treated  
23 via an on-site absorption system constructed consistent with Vermont's

1 requirements and best engineering practices. Facility solid waste is expected to be  
2 minimal, and would be collected and disposed similar to any dwelling in the town.  
3 No open burning of trash will be allowed. Heat to the building will be provided  
4 through a propane-fired or oil-fired hot air heating system. The only wastes that may  
5 require special handling would include lubricating oils and hydraulic fluids generated  
6 by the on-going maintenance of the wind turbines. All wastes generated by the  
7 operation of this facility will be collected, containerized, transported and disposed of  
8 in accordance with all applicable Vermont and Federal standards.

9 **Fluid containment.** The tower, foundation and nacelle structure would  
10 provide a measure of secondary containment. Given the lack of a watertight seal  
11 between the tower and nacelle, this containment is not complete. However, the  
12 majority of fluid released inside the nacelle would be contained inside this complex.  
13 Each nacelle is designed to contain any spills from the internal equipment.  
14 Therefore, the greatest exposure is during construction or component replacement.  
15 Oil stored on site during the construction efforts will be in approved containers,  
16 which will be 55-gallons or less. These containers will be stored in an area protected  
17 from the elements with adequate secondary containment to contain a spill of the  
18 largest container. Such containment will be sufficient to ensure the protection of the  
19 water supply, public health, and worker safety.

1    **Q    Will the project cause unreasonable soil erosion or reduction in the capacity of**  
2    **land to hold water so that a dangerous or unhealthy condition may result?**

3    Response: The Project will not cause unreasonable soil erosion, nor reduce the land's  
4    water capacity so that a dangerous or unhealthy condition will result.

5           The project will be phased to limit the amount of open and exposed soils.  
6    Further, the amount of land cleared for this project has undergone the same iterative  
7    process as the location of roads and turbines in an effort to reduce the amount of  
8    clearing as much as possible. The current amount of cleared area for this project has  
9    been reduced to approximately 120 acres. Once the construction has been completed  
10   all construction staging/laydown areas and road shoulders will be allowed to  
11   naturally re-vegetate. This represents approximately 105 acres (or 87%) of the total  
12   120 acres cleared for construction purposes. The remaining approximately 15.4 acres  
13   will remain permanently cleared and is considered to be the limit of new impervious  
14   surface.

15           As required under the NPDES Construction General Permit for  
16    construction activities that will disturb more than 5 acres of land, a project-specific  
17    Erosion Prevention and Sedimentation Control (EPSC) Plan is required. This plan  
18    will specify design elements required to stabilize erosion-prone soils and disturbed  
19    soils within the construction area of the project. Since the specific layout of the  
20    project may be modified as a result of the section 248 process, and due to on-going  
21    discussions with ANR on both erosion and stormwater issues, we are providing a  
22    number of sheets of typical erosion control practices that will likely be used for this

1 project. The detailed erosion control plan and permit will be prepared well in  
2 advance of construction. A conceptual erosion control plan is attached as ***Exhibit***  
3 ***UPC-RN-3***, and EPSC drawings at ***Exhibit UPC-RN-2***. Some of the general  
4 elements of the EPSC Plan are described here.

5 As part of our on-going development of the erosion control plans for this  
6 project, I have reviewed the *Vermont Handbook for Soil Erosion and Sediment Control on*  
7 *Construction Sites*. This site would not be considered a low-erosion potential  
8 environment, given the nature of the work to be performed and the setting, i.e., there  
9 will be locations with more than two acres disturbed at one time, there are stream  
10 crossings, and most notably the mountain slopes are frequently more than ten  
11 percent. I have thus considered the erosion potential of the situation in  
12 conceptualizing road designs for the Project.

13 Drawing C-101, sheet 4 of 5 of the preliminary project drawings (***Exhibit***  
14 ***UPC-RN-2***) is an example plan and profile design drawing, which illustrates a  
15 challenging section of the proposed access road, where erosion potential exists. The  
16 access road is designed to provide construction and crane access from Turbine No. 7  
17 downslope to Turbine No. 14. To accomplish this the proposed road reaches a  
18 maximum grade of 14.9 percent for over a quarter mile. The grading for this section  
19 of road features lengths of rock excavation and sections of fill.

20 Exposed cut and fill slopes depicted on this plan will require surface  
21 protection through the use of upslope diversion berms, rip-rap protection, and  
22 mulching and netting. Exposed rock cuts will not require protection, as they do not

1 present an erosion risk. The ditches along the roadway will be rip-rapped to resist  
2 the erosion forces of the concentrated runoff, and will have rock check dams to slow  
3 the water velocity and trap sediment. The ditches will flow to cross drainage culverts  
4 having stabilized inlets and outlets, which will convey the runoff under the road and  
5 re-distribute the runoff to adjacent natural vegetation.

6 Erosion controls will be implemented prior to construction-related soil  
7 disturbance activities being initiated within a specific area. In addition, stormwater  
8 controls will be implemented concurrently with the construction activities that  
9 require such measures (i.e., road construction). Where necessary, temporary controls  
10 will be constructed and maintained until the permanent controls are in place. At a  
11 minimum, specific techniques would include:

12 (1) Diversion Channels: There will be diversion channels, berms or dikes,  
13 installed outside the perimeter of cut areas to control runoff flowing into the  
14 excavation site. Since such cut areas will likely extend for substantial  
15 distances, there will be periodic stone or sodded channels (slope drains) to  
16 carry the water down the slope (where those cut slopes are not in bedrock),  
17 to the road ditch, through the road cross drainage and discharged through a  
18 stabilized outlet. Frequent road cross-drainage in steep terrain will reduce  
19 the water volume in the channels and help to maintain the mountainside  
20 hydrology.

21 (2) Undisturbed Buffer: Wherever possible, there will be an undisturbed buffer  
22 strip of vegetation of at least fifty feet down hill of all construction areas. As

1 this is not possible in some areas, additional measures will be employed to  
2 protect those Class 3 wetlands that are closer than 50 feet such as the use of  
3 silt fences and erosion control berms.

4 (3) Seed and Mulch: Disturbed soils will be mulched at the end of each day as  
5 necessary. The areas that have achieved finished graded slopes will be seeded  
6 and mulched within a week's time. Mulch could be: weed-free straw (placed  
7 loose on gentle slopes); an erosion control and re-vegetation mat (ECRM)  
8 that is stapled to slopes (swale bottoms, concentrated flow areas, long slopes  
9 with more rilling potential or slopes greater than 3:1 slope); or, the standard  
10 mulch incorporated into hydroseed mixes (small areas, gentle slopes). The  
11 mantra of mulching quickly and minimizing disturbance areas will be an  
12 important element on this site. During construction, the slopes will be  
13 routinely roughened to improve infiltration characteristics (typically, running  
14 a bulldozer up/down a slope). Also, the finished and seeded roadway  
15 segments will have interceptors, to reduce erosion until plants are  
16 established.

17 (4) Erosion Control Mix Berms: Erosion Control Mix Berms are an engineered  
18 mixture of shredded bark, grindings, composted bark, wood chip and soils,  
19 and have been used effectively as an alternative to silt fence. They would  
20 likely be preferred over silt fencing in less accessible locations, areas of  
21 shallow depth to bedrock, on steep slopes (where silt fence is an issue), and  
22 crossing swales (then, built like a check dam).

1 (5) Snow Fencing: Snow fencing will be placed along down gradient slopes, at  
2 least within one hundred feet of any Class 3 wetland resources. Where  
3 impacts to the Class 3 wetlands will be occurring during the construction  
4 activities, the limits of construction (hence impact) will be demarcated with  
5 additional snow fencing. Such fencing will serve not so much as an erosion  
6 control but more as a visual barrier for construction activities to prevent  
7 damage to wetlands.

8 (6) Silt Fence: Silt fence will also be installed at select locations to collect  
9 sediment. Silt fences may be used in combination with a hay bale buttress, as  
10 shown on the conceptual EPSC Plan drawings. I do not recommend the use  
11 of hay bales alone, as hay bales are frequently improperly installed.

12 (7) Downslope Dike: Downslope erosion control mix berms or dikes may be  
13 used as an alternative to silt fence on gentle slopes. Near wetland resources,  
14 downslope dikes may be used in conjunction with silt fences or other control  
15 devices. The berms could direct runoff away from wetlands; while the silt  
16 fence will serve as backup should the diversion dike become clogged during a  
17 significant rain event. The silt fence or additional snow fence will also serve  
18 as a visual cue for equipment to not disturb the dikes and other control  
19 devices. The dike could remain in place following construction to encourage  
20 infiltration of water.

1 (8) Stone Check Dams – Stone check dams will be used along the new road  
2 ditching to control ditch velocity and to trap sediment, as shown on the  
3 sample EPSCP detail sheet.

4 (9) Erosion Control/Stormwater Monitoring: Independent monitoring  
5 personnel will be employed as required in the stormwater/erosion control  
6 permit conditions, to observe, inspect and document control performance  
7 and maintenance/repair activities. All such erosion control measures will be  
8 inspected weekly and immediately following storm events of more than ½-  
9 inch rainfall as recorded at an on-site rain gage. The specifics of observation,  
10 inspection, record-keeping, maintenance and repair will also be in compliance  
11 with the specified permit conditions. I have provided a discussion of the  
12 independent monitoring and sample reporting forms in the conceptual EPSC  
13 Plan.

14 **Q. Are there areas of the construction that will require special consideration**  
15 **when it comes to erosion prevention/sediment control and stormwater**  
16 **control?**

17 Response: Areas of special consideration are wetlands, stockpiles, dust control, and  
18 sections of steep roadway.

19 Class 3 wetlands will be provided special protection in the form of additional silt  
20 fencing, erosion mix berms, erosion control barriers, and snow fencing beyond  
21 diversion dikes constructed uphill of the wetlands. These additional barriers will

1 provide effective control and containment of sediment so it does not enter the  
2 wetland areas.

3 Stockpiles require special consideration because these areas represent large piles of  
4 exposed, usually erodible materials where access is required on a frequent basis to  
5 allow construction to continue. Stockpiles will be sited on the most gentle of site  
6 gradients, as far away from wetland resources as is possible, in existing cleared areas  
7 if possible, and will be ringed with erosion control barriers.

8 Dust Control - We recommended that the project use water for dust control,  
9 dispersed from a water truck. The source of water would be the responsibility of the  
10 construction contractor. We understand that, historically, various surface water  
11 sources including the Passumpsic River, its tributaries and other local surface water  
12 sources have been used in addition to the Sheffield Municipal Well. The contractor  
13 will be responsible for any permitting involved with water withdrawal. Further, dust  
14 control will be required for concrete batching operations for the foundation  
15 construction. Again, we do not anticipate a concrete batch plant to be constructed  
16 within the project limits. The permitting of the concrete operations will also be the  
17 responsibility of the supplier.

18 Steep sections of new roadway will be more susceptible to erosion than areas with  
19 milder slope. The final design of these sections will address the velocity of the  
20 runoff and will present appropriately sized ditch rip-rap to resist the erosive forces of  
21 stormwater runoff. As I mentioned earlier, our goal is to redistribute runoff as  
22 frequently as practicable to preserve existing hydrology pattern and flows.

1 **Q. Please provide a construction sequence and identify how erosion control and**  
2 **stormwater control will be implemented.**

3 Response: The conceptual EPSC Plan (*Exhibit UPC-RN-3*) contains a sample  
4 discussion of the project construction sequencing. In form of a summary, the  
5 sequence, at its simplest, involves:

- 6 (1) Cut trees in the road and foundation construction areas; use temporary  
7 bridge crossings where necessary.
- 8 (2) Install erosion control barriers, such as silt fence and hay bales.
- 9 (3) Install diversion dikes and check dams and necessary temporary stormwater  
10 controls.
- 11 (4) Install and stabilize the culverts and stream crossings.
- 12 (5) Grub and stockpile loam, where feasible, from road and foundation  
13 construction. The accumulated loam will be reused, if possible, in the  
14 immediate vicinity of the stockpiled location; otherwise these materials will  
15 be transported off-site by the contractor unless a suitable on-site location is  
16 available.
- 17 (6) Excavate subsoils and rock; stabilize as necessary as work progresses.
- 18 (7) Build embankments to subgrade; stabilize as necessary as work progresses.
- 19 (8) Install rip-rap/trap rock on steep fill and cut slopes.

- 1           (9)     Install finish layer of road materials on top of the embankments; complete  
2                     permanent stormwater control structures.
- 3           (10)    Install salvaged loam on embankments (as available); seed and mulch.
- 4           (11)    Monitor site during turbine construction; finish clearing near turbines where  
5                     blades reach toward the woods, but do not grub.
- 6           (12)    Finish turbine assembly.
- 7           (13)    Apply suitable topdress or wood chip to construction road shoulders; apply  
8                     interceptor ditches, seed and mulch to stabilize. Finish stabilizing former  
9                     stockpile areas.
- 10          (14)    Continue monitoring site until suitably stabilized for the long-term  
11                     operations.

12   **Q     Will there be sufficient water available for the reasonably foreseeable needs of**  
13   **the Project?**

14    Response: There will be sufficient water available for foreseeable needs. First, water  
15    will be required for construction and compacting of soils and dust control. Based  
16    upon our experience, this water will be transported on-site by trucks provided by the  
17    contractor. The source of water has not been identified as of now. As discussed  
18    previously, off-site surface water sources will be utilized as a source. The contractor  
19    will be responsible for identifying and permitting, if necessary, a water withdrawal.  
20    Following construction the water demand of the project will be almost eliminated.

1 The proposed roads will only have heavy use during construction, when dust control  
2 will be used. During the remainder of the project life, the road use will be infrequent  
3 and a very low daily volume, and should not require further dust control.

4 Second, soils boring equipment used in the soils exploration program  
5 (necessary to acquire foundation design parameters) will require water, but it will be a  
6 small volume and is typically recycled during use.

7 Third, there will be the long-term staffing at the operations and maintenance  
8 building that will require potable water. This water demand would be analogous to a  
9 single family home.

10

11 **Q Will the project cause unreasonable congestion or unsafe conditions on public**  
12 **roads?**

13 Response: This question needs to be answered in terms of construction and  
14 operation/maintenance. In terms of construction, we are currently working with the  
15 Agency of Transportation to determine possible access points to the project. These  
16 are best described in the prefiled direct testimony of Cowan/Rowland/Vavrik. In  
17 terms of operation and maintenance, the project will employ on a full time basis  
18 between three and five personnel, representing 6-10 vehicle trips per day. These  
19 employees will require access to the project site, typically, during normal business  
20 hours and during periods of upset conditions. We do not feel that the personnel  
21 involved with the operation and maintenance will present an unreasonable  
22 congestion or make unsafe any public roads.

1    **Q    Have you relied on the work of any other experts concerning this project?**

2            Response: I relied on the input from Art Gillman, the wetland expert retained by  
3            UPC and Jeff Wallin, wildlife biologist also retained by UPC. In addition, I received  
4            input from UPC on the typical wind turbine construction activities, and the desired  
5            locations of the wind turbines.

6    **Q    Describe your recommendations to UPC Vermont Wind regarding the design**  
7            **and siting of the project based upon the results of your investigations and**  
8            **analyses.**

9            Response: To the extent that I have reasonably unfettered control of the micrositing  
10           of project roadways, my current recommendations have been incorporated and are  
11           represented on the “20-percent” design drawings. I have recommended:

12           (1) Road grade: Minimize grade severity wherever possible, to facilitate equipment  
13           movement and to reduce erosion potential. Maximum road grade for ridge top  
14           roads is 15%. Roads should ideally return to a 5% grade wherever an assembled  
15           crane is expected to make a turn, whether in transit along the ridge or to enter  
16           onto a dedicated crane pad.

17           (2) Road width: Ridge roads should have a width of thirty-six (36) feet for  
18           construction (consisting of a 16-foot main road width with two 10-foot  
19           shoulders to allow for crane transit); the width would be reduced through re-  
20           vegetation or the application of wood chip to a nominal width of approximately  
21           sixteen (16) feet. Access roads to the ridges will vary in width; generally, I

1 recommend a width of sixteen (16) feet, with re-vegetation at the widened road  
2 intersections, *e.g.*, intersection with the public way.

3 (3) Vegetation restoration: As noted above, roads that are constructed based upon  
4 the needs of construction-phase equipment should receive seed or wood chips  
5 over portions of that width. The road grade for its full width will be retained for  
6 potential maintenance/repair work such as replacing a damaged rotor and for  
7 eventual decommissioning, as necessary. However, it is unnecessary to maintain  
8 the full width as gravel, and so portions of the road width should be seeded and  
9 allowed to re-vegetate naturally.

10 (4) Turbine sites: Only the foundation site proper need be grubbed and thoroughly  
11 disturbed to create a crane pad and driveway. The approximate size of the crane  
12 pad is generally 40 ft by 100 feet. An additional area for the temporary laydown  
13 and storage of the turbine components is required, but the outlying areas, where  
14 only the blades of the rotor will project during assembly, can be cleared without  
15 grubbing stumps and roots, for the benefit of erosion control. Our design  
16 drawings submitted with this application show a “worse case” approach, where  
17 the entire turbine temporary laydown and assembly area is shown graded. In this  
18 way, the impacts in the final layout and construction plans will be less than  
19 submitted in the permit documents.

20 (5) Erosion control: Project temporary erosion controls must be consistent with  
21 Vermont ANR’s requirements. UPC will coordinate with the general contractor,  
22 once selected, to ensure that the contractor understands all the aspects of the

1 EPSCP, is trained in the EPSCP requirements, commits to the provisions of the  
2 plan and the requirements of the State, and monitors progress of construction to  
3 ensure the successful implementation and protection of wetland and habitat  
4 resources. UPC and their consultants should work closely with ANR in the  
5 development of the EPSCP to incorporate State requirements during the  
6 development of the final plans.

7 (6) Stormwater control: Project stormwater controls should be implemented  
8 consistent with Vermont's current regulations. A thorough watershed evaluation  
9 should be conducted, to locate potential downstream issues, and to determine  
10 waiver applicability. Also, a clear maintenance plan should be established with  
11 commitments to ensure successful implementation and protection of wetland  
12 and habitat resources, abutting undisturbed property, and the public way.

13 (7) Transport issues. Once the turbine components are set, or at least the upper  
14 limits of shipping weights and dimension established, further consultation should  
15 proceed with VTAOT. In particular, VTAOT should be consulted on the  
16 proposed delivery route to evaluate the proposed loads on bridges and  
17 structures, and to prepare for public safety.

18 **Q Does this conclude your testimony at this time?**

19 Response: Yes, it does.